



Insulation fastened every 2 sq. ft. in adhered membrane area, 6" from low point of valley. (typical)

Comments: Welds not be located at low point of valley



MFRS Securement at Valley Roofing System Detail

Scale: Not to scale
Date: August, 2016
Detail No.: H-E-021